



SYSTEM NOTES	
KEYNOTE	DISCRPTION
F1	3 1/2" REINFORCED CONCRETE SLAB OVER METAL DECK & STRUCTURE - (REF. STRUCTL DNG'S)
F2	6" CONCRETE SLAB-ON-GRADE
F3	RECYCLED COMPOSITE DECKING OVER WOOD & STEEL STRUCTURE (RE: STRUCTURAL DNG'S)
F4	4" PERMIABLE CONCRETE SIDEWALKS
W1	REINFORCED CONCRETE FOUNDATION WALLS AND FOOTINGS - (RE: STRUCTURAL DNG'S)
W2	4" STONE VENEER, 1" AIR CAVITY, AIR BARRIER, 1/2" EXTERIOR SHEATHING, PRE. ENG. MTL. BLD. STRUCTURE, 5 1/2" (R-19) BATT INSULATION, & INTERIOR PRE. - FIN. MTL. LINER PANEL
W2A	4" STONE VENEER, 1" AIR CAVITY, AIR BARRIER, 1/2" EXTERIOR SHEATHING, 1 1/2" HAT CHANNELS, 6" METAL STUDS @ 16" O.C., 5 1/2" (R-19) BATT INSULATION, & INTERIOR PRE. - FIN. MTL. LINER PANEL
W3	PRE. ENG. MTL. WALL PANEL ON PRE. ENG. MTL. BLD. STRUCTURE, 5 1/2" (R-19) BATT INSULATION, & INTERIOR PRE. - FIN. MTL. LINER PANEL
W4	3 5/8" MTL. STUDS @ 16" O.C. w/ 5/8" TYPE 'X' GYPSUM BOARD ON BOTH SIDES
W5	3 5/8" MTL. STUDS @ 16" O.C. w/ 5/8" MOISTURE RESISTANT GYPSUM BOARD ON NET SIDE & 3" SOUND BATT INSULATION
W6	3 5/8" MTL. STUDS @ 16" O.C. w/ 5/8" TYPE 'X' GYPSUM BOARD ON BOTH SIDES - (ONE HOUR ASSEMBLY)
W7	3 5/8" MTL. STUDS @ 16" O.C. w/ 5/8" TYPE 'X' GYPSUM BOARD ON INTERIOR SIDE
W8	4" STONE VENEER ON 8" CMU BLOCK
W9	4" STONE VENEER BOTH SIDES OF 8" CMU BLOCK
C1	EXPOSED STEEL STRUCTURE - PAINT
C2	PAINTED 1/2" TYPE 'X' GYPSUM BOARD
C3	2 x 4 SUSPENDED ACOUSTICAL CEILING TILE SYSTEM
C4	2 x 4 VINYL COATED SUSPENDED ACOUSTICAL CEILING TILE SYSTEM
C5	2 x 4 VINYL COATED GYP CEILING TILE SYSTEM
C6	PREFINISHED METAL LINER PANEL
R1	PRE - FINISHED METAL ROOF OVER STRUCTL STEEL PRE. ENG. MTL. BLD. STRUCTURE, 4" (R-30) BATT INSULATION, & PRE - FINISHED MTL. LINER PANEL
R2	PRE - FINISHED METAL ROOF OVER EXTERIOR STRUCTL STEEL PRE. - ENG. MTL. BLD. STRUCTURE

KEYNOTES	
NUMBER	DESCRIPTION
1	CHANGE IN CEILING / STRUCTURE ABOVE
2	14" LIGHT TUBE WITH EXTENSIONS
3	PRE-FINISHED METAL FLASHING, GUTTER AND / OR DOWNSPOUT
4	4" (R-35) BATT INSULATION & P.F. METAL LINER PANEL
7	PRE-FINISHED INSULATED WINDOW UNIT (TYPICAL)
10	PRE. FIN. METAL SIGN GUARD (TYP.)
11	RECESSED FLOOR MAT
12	42" HIGH 1 1/2" STEEL GUARDRAIL w/ 4" O.C. W/WF
14	DECK (ABOVE)
15	ROOF STRUCTURE ABOVE
18	WALL CABINETS - COORD. W/ FOOD SERVICE VENDOR
19	BASE CABINETS - COORD. W/ FOOD SERVICE VENDOR
20	SINK, FLOOR DRAIN, FLOOR SINK, ETC. - (RE: M.E.P. DNG'S)
21	SHELVING
25	PAINTED STEEL HAND RAILS, GUARD RAILS, & STRUCTL. STEEL - (REF. STRUCTURAL DNG'S.)
28	GALVANIZED STAIR TREADS AND RISER
29	4" STONE VENEER
31	FUTURE PHOTOVOLTAIC PANELS MOUNTED ON ROOF
34	PAINTED STRUCTURAL STEEL - (RE: STRUCTURAL DNG'S)
35	STONE CAP & P.F. FLASHING
37	FIREPLACE CHIMNEY
38	PADDLE FANS (RE: ELEG DNG'S)
40	SIDEWALK OF PERMIABLE CONCRETE (RE: CIVIL DNG'S)
41	RECYCLED SHIP'S MAST (BY OTHERS)

1 NORTH
 1/8" = 1'-0"
 2148 SF
MAIN LEVEL

GENERAL NOTES
 1. OWNER TO PROVIDE ALL ROCK
 2. OWNER TO PROVIDE SEPTIC
 3. SOLAR PANELS FOR FUTURE PHASE